

June 26, 2012

Chris Ida U.S. Forest Service Arapaho and Roosevelt National Forests 2150 Centre Avenue, Building E Fort Collins, Colorado, 80526

**Subject:** Report for Rollinsville Work Center Asbestos Survey Project

Dear Mr. Ida:

RMC Consultants, Inc. (RMC) is pleased to submit this asbestos containing material (ACM) survey report for the Rollinsville Work Center in Rollinsville, Colorado.

On June 6, 2012, RMC conducted an inspection for the presence of ACMs in the construction building materials at the above referenced site. The inspection consisted of the following:

- Visually examine accessible areas and identify the locations of suspect ACM.
- Collect and analyze representative bulk samples of materials suspected of containing asbestos.
- Document ACM quantities.
- Generate a final report documenting sample locations, analysis results, conditions, ACM quantities, and recommendations.

If you have any questions about this report, please do not hesitate to contact me at 303.980.4101 or by email at cmurray@rmc-consultants.com.

Sincerely,

RMC Consultants, Inc.

Claude D. Murray, PG, PMP

Senior Project Manager

Enclosure: ACM Survey Report

12295 W. 48<sup>th</sup> Avenue, Unit A Wheat Ridge, CO 80033 303.980.4101 (t), 303.980.4107 (f) www.rmc-consultants.com



# **Table of Contents**

1	EXECUTIVE SUMMARY	2
2	SITE DESCRIPTION	2
3	METHODOLOGY	З
3.1	Homogeneous Areas/Materials	
3.2	Sample Collection	3
3.3	Analytical Laboratory Information	4
4	CERTIFICATION	4
5	AREAS UNABLE TO BE SAMPLED	4
6	RESULTS	4
6.1	Asbestos-Containing Materials	2
6.2	Non-Asbestos-Containing Materials	5
7	RECOMMENDATIONS	5
<b>Tables</b> Table 1	Summary of Asbestos Building Inspection and Analytical Results	
Figures		
Figure 1	Survey Area Location Map	
Figure 2	Men's Bunkhouse (#0701) Plan	
Figure 3	Women's Bunkhouse (#0702) Plan	
Figure 4	Storage Shed (#0705) Plan	
Figure 5	Storage Shed (#0706) Plan	
Figure 6	Pump House Plan	

# **Appendices**

Certificates

Laboratory Analytical Report

June 26, 2012



# 1 EXECUTIVE SUMMARY

On June 6, 2012, RMC Consultants, Inc. (RMC) performed an asbestos-containing material (ACM) inspection at the Rollinsville Work Center in Rollinsville, Colorado.

ACM is defined by state and federal regulations as "any material that contains greater than 1% asbestos." All suspect ACMs sampled during the inspection were analyzed by Polarized Light Microscopy (PLM), EPA Method 600/M4-82-020. The following materials were shown through analysis to be ACM:

- Brown/white floor tile in entry and toilet rooms of building 0701.
- Brown floor tile with black mastic in the bedrooms of building 0701.
- Tan floor tile with black mastic in the family and bedrooms of building 0702.
- Tan/multi-colored tile with black mastic in the dining room and kitchen of building 0702.
- Joint compound/texture in the family room and bedrooms of building 0702.

Laboratory analysis of some suspect ACM was reported to contain less than 1 percent (%). Methodologies resulting in determination of less than 1% materials included initial PLM analysis and follow-up PLM point-count analysis. The following materials were reported through analysis to have asbestos present at concentrations less than 1%:

- Mastic on the brown/white floor tile in entry and toilet rooms of building 0701.
- Glazing on the exterior window of building 0705.

RMC's inspection identified ACMs within buildings 0701 and 0702. RMC's review identified ACM in good condition.

Identified ACM can be managed until such time as demolition, renovation, or repair requires their removal. If demolition, renovation, or repair to an ACM is to occur, they must be removed by certified asbestos workers or specially trained professionals. Should damage to one of the ACM be identified, RMC recommends that the area be secured to prevent further damage, until review by an Asbestos Hazard Emergency Response Act (AHERA) accredited Building Inspector.

#### **2 SITE DESCRIPTION**

The subject site included the Work Center property located on National Forest road NF-105 in Rollinsville, Colorado. The property included two residential buildings, two storage sheds, one pump house, and two areas where buildings formerly stood (see Figure 1). The residential buildings consisted of a Men's Bunkhouse (building number 0701) and Women's Bunkhouse (building number 0702) which were single-story houses with crawl spaces and attics. The two storage sheds and the pump house were wood and/or rock structures on concrete slabs. The date of original construction was not ascertained. Typical interior construction consists of sheetrock and vinyl tile flooring. Typical exterior construction consists of wood or vinyl siding and asphalt shingles.



# 3 METHODOLOGY

The AHERA regulations specify sampling density protocol based on the quantity and type of material. The sampling protocol and methodology employed by RMC is outlined within this section. Sample locations in the facility were selected by RMC to be representative of the various homogeneous materials. RMC inspectors collected samples at selected locations using a random sampling scheme. As destructive testing is outside of the scope of many projects, samples may have been collected in obscure or hidden locations whenever practical, which does limit the definition of a randomly selected sample location.

Sample density, to prove that a material is a non-ACM, was selected using the following criteria:

- For surfacing materials, a minimum of 3 bulk samples collected for homogeneous areas less than 1,000 square feet (ft²). At least 5 bulk samples collected for homogeneous areas between 1,000 ft2 and 2,000 ft². Seven or more bulk samples collected for homogeneous areas greater than 5,000 ft².
- For thermal system insulation (TSI), not assumed to be ACM, within the same homogeneous area, 3 bulk samples were collected, or in a manner sufficient to identify the suspect material as ACM or non-ACM.
- For suspect miscellaneous material, not assumed to be an ACM, samples were collected in a manner sufficient to determine whether the material was ACM or non-ACM.

# 3.1 Homogeneous Areas/Materials

For this inspection report, homogeneous areas/materials were developed using visual observations made in the field regarding material appearance, texture, size, color, construction era, and/or manufacturers' labels. Suspect homogeneous materials were then sampled to determine if they contain asbestos or are non-asbestos materials based on the laboratory results. The following system was used to identify homogeneous materials:

- Materials that were sampled and reported as ACM via PLM analytical methods and
  materials that were applied during the same construction/renovation phase and appeared
  the same with respect to color, texture, and/or size were assumed to be homogeneous.
  Homogeneous materials are grouped together in the data tables presented in this report.
- Materials which were assumed to contain asbestos based on the experience and expertise
  of the Inspector were considered homogeneous in the space where this assumption was
  made.
- Materials which were sampled and reported as negative for asbestos content were considered homogeneous based on AHERA protocol.

#### 3.2 Sample Collection

At the point of sample collection, the sample was placed in a sample container and coded by the inspector. The location was noted on the building floor plan and the identification recorded on the survey record.

The sampling tool was then cleaned to prevent contamination of subsequent samples. Any debris was cleaned up and sealed in plastic for disposal. On completion of the inspection, samples are counted and



their numbers placed on the chain-of-custody sheet. The inspector signed the chain-of-custody sheet. The chain-of-custody sheet remains with the samples from collection through analysis.

# 3.3 Analytical Laboratory Information

Asbestos samples were analyzed by Reservoirs Environmental, Inc., a National Voluntary Laboratory Accreditation Program (NVLAP) accredited laboratory located in Denver, Colorado (#101896-0). Polarized Light Microscopy (PLM) method EPA 600/M4-82-020 was used for analysis of asbestos samples. AHERA regulations require laboratories to analyze suspect ACM using PLM methods. Laboratories which analyze bulk samples must be accredited. Recognized accreditation is provided by the National Institute of Standards and Technology (NIST) under the NVLAP.

## 4 CERTIFICATION

RMC certifies that the inspection is consistent with federal, state, and local regulations governing project-specific conditions and was performed using recognized procedures and standards of the industry.

Mr. Jason Kahlert of RMC conducted the asbestos building inspection. Mr. Kahlert is accredited by the Environmental Protection Agency (EPA) under the AHERA and certified by the Colorado Department of Public Health and Environment (CDPHE) as an Asbestos Building Inspector (see copies of certificates attached). Mr. Kahlert's accreditation and certification numbers are as follows:

AHERA Building Inspector #2/12BIGHP3

Expiration Date: 2/8/2013

CDPHE Building Inspector #19162

Expiration Date: 3/9/2013

## 5 AREAS UNABLE TO BE SAMPLED

RMC did not access areas that required demolition to access, i.e., below well-adhered carpeting, above hard lid ceilings, and inside wall voids and pipe chases. Attic and crawl space access was gained in buildings 0701 and 0702.

# 6 RESULTS

#### 6.1 Asbestos-Containing Materials

Twenty six (26) bulk samples from twenty two (22) suspect materials were collected on June 6, 2012, and submitted to the laboratory for analysis. The following is a summary of building materials found to contain greater than one percent asbestos (ACM by regulatory definition):

- Brown/white floor tile in entry/toilet rooms of building 0701 contains 3% chrysotile (asbestos).
- Brown floor tile with black mastic in the bedrooms of building 0701 contain 10% chrysotile.
- Joint compound in the bedrooms of building 0701 contain up to 1.75% chrysotile.



- Tan floor tile with black mastic in the family and bedrooms of building 0702 contain 10% chrysotile.
- Tan/multi-colored tile with black mastic in the dining room and kitchen of building 0702 contain 10% chrysotile.
- Joint compound/texture in the family/bedrooms of building 0702 contains up to 2.25% chrysotile.

## 6.2 Non-Asbestos-Containing Materials

Two former building areas (see Figure 1) were visually inspected for evidence of ACM. No ACM was observed at these former building locations.

The following is a summary of building materials found to contain no ACM or less than one percent ACM:

- Sheetrock
- White wall texture
- Various style/color vinyl tiles
- Counter laminate with adhesives
- Asphalt shingles and backing
- Attic insulation
- Black/gray granular cementitious material (fireplace fireproofing)
- Carpets
- Window glazing
- Wire insulation
- Yellow sealing foam

Table 1 lists individual functional spaces of the buildings, the suspect materials identified in that functional space, whether the suspect material was identified by analysis to be ACM, an estimated amount of each suspect material for the functional space, and includes condition and hazard ratings based on subjective observations made by our representatives. Table 1 also lists the homogeneous material sample numbers, sample locations, suspect material descriptions, and the analytical results for each sample. This table summarizes the results from the attached Bulk Asbestos Analysis Report.

The two areas where buildings formerly stood (former sign fabrication building area and the southern former building area [Figure 1]) were visually inspected for the presence of ACMs. No evidence of ACMs was observed at these two locations.

# 7 RECOMMENDATIONS

Laboratory analysis confirmed the presence of asbestos in flooring tiles and wall texture/joint compound in both Bunkhouse buildings. The ACM's identified in the buildings at the Rollinsville Work Center are in good condition. These materials may be managed under a site-specific asbestos Operations and Maintenance (O&M) plan. If renovation, repair, or demolition requires the removal of



ACM's, this work is required to be performed by a properly licensed abatement contractor using properly trained asbestos workers. Should damage to one of the ACM be identified, RMC recommends that the area be secured to prevent further damage, until review by an AHERA accredited Building Inspector.

RMC shall not be responsible for non-identification of asbestos containing materials that are not common to the construction industry; require destructive testing, demolition, and/or disassembly of equipment to access; and for information prepared by others and supplied by the Owner. The identification of asbestos was performed on the day the facility was inspected. RMC shall not be held responsible for changed or differing site conditions, which may have occurred since the performance of this inspection.

Table 1
Summary of Asbestos Building Inspection and Analytical Results, Rollinsville Work Center

Building ID	Functional Space	Homogeneous Material Description	Contains Asbestos (Yes/No)	Sample ID	Lab ID	Estimated Quantity Units	Material Condition	Hazard Category ‡	Asbestos Content (%)†
0701	Kitchen/Shower	Floor Tile	No	RWC-0701-01	EM 137439	200 ft <sup>2</sup>	Not Damaged	0	ND
0701	Kitchen	Counter Laminate	No	RWC-0701-02	EM 137440	20 ft <sup>2</sup>	Not Damaged	0	ND
0701	Entry/Toilet Room	Floor Tile	Yes	RWC-0701-03	EM 137441	100 ft <sup>2</sup>	Not Damaged	3	Mastic - <0.25 Tile - 3
0701	Bedroom 1 & 2	Floor Tile	Yes	RWC-0701-04	EM 137442	440 ft <sup>2</sup>	Not Damaged	3	Mastic - 10 Tile - 8
0701	Roof	Shingle	No	RWC-0701-05	EM 137443	800 ft <sup>2</sup>	Not Damaged	0	ND
0701	Attic	Blown-In Insulation	No	RWC-0701-07	EM 137444	800 ft <sup>2</sup>	Not Damaged	0	ND
			Yes	RWC-0701-08	EM 137445		Not Damaged	1	Compound - 1.25 Drywall - ND
0701	Bedroom 1 & 2, Entry	Wall/Ceiling	Yes	RWC-0701-09	EM 137446	1,650 ft <sup>2</sup>	Not Damaged	1	Tape - ND Compound - 1.75 Joint Compound - 1.5 Drywall - ND
			No	RWC-0701-10	EM 137447		Not Damaged	1	ND
0702	Bathroom	Floor Tile	No	RWC-0702-01	EM 137448	60 ft <sup>2</sup>	Damaged	0	ND
0702	Fireplace Insulation	Concrete	No	RWC-0702-02	EM 137449	48 ft <sup>2</sup>	Not Damaged	0	ND
0702	Family/Bedrooms	Floor Tile	Yes	RWC-0702-03	EM 137450	600 ft <sup>2</sup>	Not Damaged	3	Mastic - 10 Tile - 8
0702	Kitchen	Counter Laminate	No	RWC-0702-04	EM 137451	20 ft <sup>2</sup>	Not Damaged	0	ND
0702	Kitchen/Dining Room	Floor Tile	Yes	RWC-0702-05	EM 137452	300 ft <sup>2</sup>	Not Damaged	3	Mastic - 10 Tile - 8
			No	RWC-0702-06	EM 137453	_	Not Damaged	0	ND
0702	Family Room	Carpet	No	RWC-0702-07	EM 137454	72 ft <sup>2</sup>	Not Damaged	0	ND
			No	RWC-0702-08	EM 137455		Not Damaged	0	ND
0702	Roof	Shingle	No	RWC-0702-09	EM 137456	1,120 ft <sup>2</sup>	Not Damaged	0	ND
			Yes	RWC-0702-14	EM 137457		Not Damaged	1	Texture - 1.75 Paint/Drywall - ND
0702	Bedrooms 1 & 2, Family Room	Wall/Ceiling	Yes	RWC-0702-15	EM 137458	1,900 ft <sup>2</sup>	Not Damaged	1	Texture - 2 Paint/Drywall - ND
			Yes	RWC-0702-16	EM 137459		Not Damaged	1	Compound - 2.25 Paint/Drywall - ND
0705	Exterior Window	Glazing	No	RWC-0705-01	EM 137460	<1 ft <sup>2</sup>	Not Damaged	0	Trace
0706	Lighting	Wire Insulation	No	RWC-0706-01	EM 137461	15 ft	Not Damaged	0	ND
0706	Exterior Window	Glazing	No	RWC-0706-02	EM 137462	<1 ft <sup>2</sup>	Not Damaged	0	ND
PH	Floor Penetration	Foam sealer	No	RWC-PH-01	EM 137463	<1 ft <sup>3</sup>	Not Damaged	0	ND
PH	Roof	Shingle With Felt/Resin	No	RWC-PH-02	EM 137464	81 ft <sup>2</sup>	Not Damaged	0	ND

#### ‡ Hazard Category:


- 0 = No hazard material does not contain asbestos
- 1 = ACM with potential for damage
- 2 = ACM with potential for significant damage
- 3 = Damaged or significantly damaged asbestos-containing miscellaneous material
- 4 = Damaged or significantly damaged asbestos-containing thermal system insulation
- 5 = Damaged or significantly damaged asbestos-containing surfacing material


PH = Pump House


ND = Not Detected.


Materials containing 1 percent of asbestos or less are not considered to be asbestos-containing materials by the USEPA.

<sup>† =</sup> Asbestos content is indicated as an approximate percent by area.











# Legend

(+) = Asbestos-Containing Sample

(-) = Non-Asbestos Sample Scale As Shown

Date: 6/20/12 Drawn By: JLK


Checked By: CDM





Storage Shed (#0705) Plan

**ROLLINSVILLE WORK CENTER ACM SURVEY** ARAPAHO & ROOSEVELT NATIONAL FORESTS, **COLORADO** 

FIGURE 4







# GOBBELL HAYS PARTNERS, INC.

10500 East 54th Avenue, Suite J  **Denver**, CO 80239 Ph. (303) 574-0082  **Fax** (303) 574-0061

# **CERTIFIES THAT**

# **JASON KAHLERT**

Has successfully completed

The 24-hour **EPA-APPROVED AHERA ASBESTOS COURSE** for Building Inspector and has passed the required examination in that discipline.

This course is EPA-approved under Section 206 of the Toxic Substances Control Act (TSCA) and meets the requirements of Colorado Regulation No. 8. Gobbell Hays Partners, Inc. Purchased MCA Environmental, Inc. and course approval can be found in the EPA directory under MCA Environmental, Inc. listed as training provider #931.

Course Date: 2/6/2012-2/8/2012

Exam Date: 2/8/2012 Certificate No.: 2/12BIGHP3 Expiration Date: 2/8/2013 1618.0

Wade E. Anderson - Director

# STATE OF COLORADO

# ASBESTOS CERTIFICATION\*

Colorado Department of Public Health and Environment Air Pollution Control Division

This certifies that

# Jason Kahlert

**Certification No: 19162** 

has met the requirements of 25-7-507, C.R.S. and Air Quality Control Commission Regulation No. 8, Part B, and is hereby certified by the state of Colorado in the following discipline:

# **Building Inspector\***

Issued: 3/9/2012

**Expires on: 3/9/2013** 

Authorized APCD Representative

\* This certificate is valid only with the possession of a current Division-approved training course certification in the discipline specified above.

SEAL



June 21, 2012 Laboratory Code: RES Subcontract Number: NA

Laboratory Report: RES 237422-1,2
Project # / P.O. # F12.006.015.000

Project # / P.O. # E12.006.015.0001 Project Description: Rollinsville, CO

RMC Consultants, Inc 12295 W. 48th Ave, Unit A Wheat Ridge, CO 80033

Dear Customer,

Reservoirs Environmental, Inc. is an analytical laboratory accredited for the analysis of Industrial Hygiene and Environmental matrices by the National Voluntary Laboratory Accreditation Program (NVLAP), Lab Code 101896-0 for Transmission Electron Microscopy (TEM) and Polarized Light Microscopy (PLM) analysis and the American Industrial Hygiene Association (AIHA), Lab ID 101533 - Accreditation Certificate #480 for Phase Contrast Microscopy (PCM) analysis. This laboratory is currently proficient in both Proficiency Testing and PAT programs respectively.

Reservoirs Environmental, Inc. has analyzed the following samples for asbestos content as per your request. The analysis has been completed in general accordance with the appropriate methodology as stated in the attached analysis table. The results have been submitted to your office.

**RES 237422-1,2** is the job number assigned to this study. This report is considered highly confidential and the sole property of the customer. Reservoirs Environmental, Inc. will not discuss any part of this study with personnel other than those of the client. The results described in this report only apply to the samples analyzed. This report must not be used to claim endorsement of products or analytical results by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without written approval from Reservoirs Environmental, Inc. Samples will be disposed of after sixty days unless longer storage is requested. If you have any questions about this report, please feel free to call 303-964-1986.

Sincerely,

Jeanne Spencer

President

Analyst(s):

Paul D. LoScalzo Wenlong Liu
Michael Scales Adam Humphreys
Anita Grigg Robert R. Workman Jr.

Bethany Nichols Anya Angst

NVLAP Lab Code 101896-0 TDH Licensed Laboratory # 30-0136

# TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 237422-1,2

Client: RMC Consultants, Inc
Client Project Number / P.O.: E12.006.015.0001
Client Project Description: Rollinsville, CO
Date Samples Received: June 8, 2012

Analysis Type: PLM, Short Report

Turnaround: 3-5 Day

Date Analyzed: June 14, 2012

ND=None Detected

TR=Trace, <1% Visual Estimate

Client	Lab	L .			Asbestos	Content	Non	Non-
Sample Number	ID Number	A Y E R	Physical Description	Sub Part (%)	Mineral	Visual Estimate (%)	Components	Components (%)
RWC-0701-01	EM 137439	Α	Gray/pink tile w/ clear mastic	100		ND	2	98
RWC-0701-02	EM 137440	Α	Multi-colored resinous material w/ brown adhesive	100		ND	50	50
RWC-0701-03	EM 137441	Α	Yellow/black mastic		Chrysotile <i>Point Count</i>	TR <0.25	0	100
		В	Brown/white tile	90	Chrysotile	3	0	97
RWC-0701-04	EM 137442	A B	Black mastic Brown tile		Chrysotile Chrysotile	10 8	0 0	90 92
RWC-0701-05	EM 137443	Α	Red/gray shingle	100		ND	10	90
RWC-0701-07	EM 137444	Α	Gray insulation	100		ND	80	20
RWC-0701-08	EM 137445	Α	Tan compound w/ white paint		Chrysotile	3	0	97
		В	Tan/white drywall	80	Point Count	1.25 ND		90

NVLAP Lab Code 101896-0 TDH Licensed Laboratory # 30-0136

# TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 237422-1,2

Client: RMC Consultants, Inc
Client Project Number / P.O.: E12.006.015.0001
Client Project Description: Rollinsville, CO
Date Samples Received: June 8, 2012

Analysis Type: PLM, Short Report

Turnaround: 3-5 Day

Date Analyzed: June 14, 2012

ND=None Detected

TR=Trace, <1% Visual Estimate

Client	Lab	L			Asbestos	Content	Non	Non-
Sample	ID Number	Α		Sub			Asbestos	Fibrous
Number		Υ	Physical	Part				Components
		E	Description	(%)	Mineral		Components	(%)
		R				Estimate (%)	(%)	
RWC-0701-09	EM 137446	Α	White tape	5		ND	95	5
		В	White compound w/ gray/multi-colored	10	Chrysotile	3	0	97
			paint					
					Point Count	1.75		
		С	White joint compound	10	Chrysotile	4	0	96
					Point Count	1.5		
		D	Tan/white drywall	75		ND	10	90
RWC-0701-10	EM 137447	Α	White texture w/ white paint	10		ND	0	100
KWC-0701-10	LIVI 137447	В	Tan/white drywall w/ white paint	90		ND ND		90
			ran/winte drywan w/ winte paint	90		ND	10	90
RWC-0702-01	EM 137448	Α	Brown/white vinyl w/ tan fibrous backing &	100		ND	15	85
			yellow mastic					
RWC-0702-02	EM 137449	Α	Black/gray granular cementitious material	100		ND	0	100
DWC 0700 00	EM 407450	٨	Dlock mostic	0	Ola a a til a	40	0	00
RWC-0702-03	EM 137450	A	Black mastic	2	Chrysotile	10	0	90 92
		В	Tan tile	98	Chrysotile	8	l 0	92
RWC-0702-04	EM 137451	Α	White/pink fibrous resinous material w/	100		ND	50	50
			yellow adhesive					

NVLAP Lab Code 101896-0 TDH Licensed Laboratory # 30-0136

# TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 237422-1,2

Client: RMC Consultants, Inc
Client Project Number / P.O.: E12.006.015.0001
Client Project Description: Rollinsville, CO
Date Samples Received: June 8, 2012

Analysis Type: PLM, Short Report

Turnaround: 3-5 Day

Date Analyzed: June 14, 2012

ND=None Detected

TR=Trace, <1% Visual Estimate

Client	Lab	L			Asbestos	Content	Non	Non-
Sample	ID Number	Α		Sub			Asbestos	
Number		Υ	Physical	Part				Components
		E	Description	(%)	Mineral		Components	
		R				Estimate (%)	(%)	
RWC-0702-05	EM 137452	A B	Black mastic Tan/multi-colored tile		Chrysotile Chrysotile	10 8	0	90 92
RWC-0702-06	EM 137453	Α	Gray carpet	100		ND	70	30
RWC-0702-07	EM 137454	Α	Tan carpet	100		ND	65	35
RWC-0702-08	EM 137455	Α	Blue carpet	100		ND	75	25
RWC-0702-09	EM 137456	A B	Brown/gray shingle Brown/black shingle	40 60		ND ND		
RWC-0702-14	EM 137457	Α	Tan texture	5	Chrysotile <i>Point Count</i>	4 1.75	0	96
		В	White/yellow paint	10		ND		100
		С	Tan/white drywall	85		ND	10	90

NVLAP Lab Code 101896-0 TDH Licensed Laboratory # 30-0136

# TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 237422-1,2

Client: RMC Consultants, Inc
Client Project Number / P.O.: E12.006.015.0001
Client Project Description: Rollinsville, CO
Date Samples Received: June 8, 2012

Analysis Type: PLM, Short Report

Turnaround: 3-5 Day

Date Analyzed: June 14, 2012

ND=None Detected

TR=Trace, <1% Visual Estimate

Client	Lab	L.			Asbestos	Content	Non	Non-
Sample Number	ID Number	A Y E	Physical Description	Sub Part (%)	Mineral	Visual	Asbestos Fibrous Components	Components
		R	Doddipuon	(70)	illinorui	Estimate (%)		
RWC-0702-15	EM 137458	Α	Pink/multi-colored paint	3		ND	0	100
		В	Tan texture	17	Chrysotile	4	0	96
			- /	2.0	Point Count	2	4.0	
		С	Tan/white drywall	80		ND	10	90
RWC-0702-16	EM 137459	Α	White/multi-colored paint	5		ND	0	100
		В	White tape	5		ND	95	5
		С	Tan compound	10	Chrysotile Point Count	4	0	96
		D	Tan joint compound	10	Chrysotile	4	0	96
					Point Count	2.25		
		Е	Tan/white drywall	70		ND	10	90
RWC-0705-01	EM 137460	Α	Gray granular material w/ brown/multi- colored paint	100	Chrysotile	TR	TR	100
RWC-0706-01	EM 137461	Α	Gray/multi-colored wire insulation	100		ND	50	50
RWC-0706-02	EM 137462	Α	White granular material w/ brown/multi- colored paint	100		ND	0	100

NVLAP Lab Code 101896-0 TDH Licensed Laboratory # 30-0136

# TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 237422-1,2

Client: RMC Consultants, Inc
Client Project Number / P.O.: E12.006.015.0001
Client Project Description: Rollinsville, CO

Date Samples Received: June 8, 2012
Analysis Type: PLM, Short Report

Turnaround: 3-5 Day

Date Analyzed: June 14, 2012

ND=None Detected

TR=Trace, <1% Visual Estimate
Trem-Act=Tremolite-Actinolite

Client	Lab	L.		ı.	Asbestos	Content	Non	Non-
•	ID Number	Α		Sub			Asbestos	
Number		Υ	Physical	Part			Fibrous	Components
		Е	Description	(%)	Mineral	Visual	Components	(%)
		R				Estimate (%)	(%)	
RWC-PH-01	EM 137463	Α	Yellow foam	100		ND	0	100
RWC-PH-02	EM 137464	A B	Brown/multi-colored shingle Black felt w/ green resinous material	45 55		ND ND		90 50

þ

Page\_

Due Date: し・1 ユ - し・1 山

Due Time:

# 5801 Logan St. Denver, CO 80216 - Phr. 303 964-1986 - Fax 303-477-4275 - Toll Free :886 RESI-ENV

INVOICE TO: (IF DIFFERENT) Pager: 303-509-2098

CONTACT INFORMATION

3 Mac-Consultants, com Number (Labora LAB NOTES: Yes / No Use Only received and will not be responsible for errors or omissions in calculations resulting from the inaccuracy of original data. By signing client/company representative agrees that submission of the following samples for requested in a 1.5% monthly interest surcharge. Initials Initials Yes / No Wiftery 303. 480.4101 [32c ۲۷ (۲ Drinking Water = DW | Waste Water = WW 1(39 138 218 1327 \*\*ASTM E1792 approved wipe media only\*\* 707 Collected 130 60 60 54 1343 Wipe = W Bulk = B Paint = P Yes / No VALID MATRIX CODES On 10e Time Time 21/9/19 Collected O = Other Sample Condition: Cell/pager: Phone: Swab = SW # Containers Soil = S Dust = D Temp. (F°) Air = A Q Matrix Code S 40 Ø) Ś 3 9 0 ζC) 87 8 Final Data Deliverable Email Address: JKq MI Prt Б91**A** \ (Д) Date Date Sample Volume SAMPLER'S INITIAL'S OR OTHER NOTES 303, 504.3420 303. 980. 4101 303. 980. 4107 Identification, Quantification , -/+ :bloM Contact: Jason Kahlert Quantification 10 4 Quantification 10 Quantification Phone (Email) Fax Phone Email Fax REQUESTED ANALYSIS or Quantification +/- or Quantification 2) 7:09 Listeria: +/--/+ : 7H:731 O iloo. B Cell/pager: Phone: ORGANICS - METH 1136 Carrier Welding Fume, Metals Scan AST ARAS, TCLP, METALS - Analyte(s) Date/Time: (Additional samples shall be listed on attached long form.) Respirable DUST - Total, Contact Contact 7400A, 7400B, OSHA - WOo Semi-quant, Micro-vac, ISO-Indirect Preps AHERA, Level II, 7402, ISO, +/-, Quant, الامتلجة PLM - Short report, Long report, Point Count 2 Initials Initials ή 5 Day Additional \*\*Prior notification Is required for RUSH PRIORITY (Next Day) X STANDARD 3 Day rakoy injohty, subject to faboratory volume and are not great freed apply for attentiours, weekeling and holifayers Time Time 3-5 Day Company Address: Date/Time: 48 년 (Sample ID's must be unique) MICROBIOLOGY LABORATORY HOURS: Weekdays: 9am - 6pm 3-5 Day 2 Day Date Date 24 Hr CHEMISTRY LABORATORY HOURS: Weekdays: 8am - 5pm \_\_\_\_ RUSH\_\_\_ 24 hr. \_\_\_3-5 Day (Rush PCM = 2hr, TEM = 6hr.) ASBESTOS LABORATORY HOURS: Weekdays: 7am - 7pm RUSH 5 day 10 day Unita .48 Hr. 24 hr. RUSH 3 day roject Number and/or P.O.#: E12,000,015,000 Phone Email Fax Phone Email Fax 48 th Ave RUSH (Same Day) 2 Rollinsville, CO 24 hr. Consultants , Inc 3 0 Turnaround times establish a laboratory priority. +0 生のモ NOTE: REI will analyze incoming samples based u analysis as indicated on this Cheff of Custody shal 03 705 () () 00 0 0 Salmonella, Listeria, E.coli, APC, Y & M 100 0 E.coli O157;H7, Coliforms, S.aureus 12040 LO 838 3707 Client sample ID number つ よ つ RWC>0701 りける 10£0-2m8 -070 兄をいっていると **尽きり-040** でより、ションの RUC-0701 RCRA 8 / Metals & Welding Number of samples received: Laboratory Use Only Received By: roject Description/Location: Relinquished By: +130/3 Special Instructions Contact Contact 55221 と さ と Fume Scan / TCLP RUC-PLM, PCM / TEM ج آگ えること Metal(s) / Dust Organics Results: Address: N ന 4 ĸ Ø œ o

Oue Date:	Oue Time:
ቯ	ቯ

5801 Logan St. Denver, CO 80216 - Phr. 303 964-1986 - Fax 303-477-4275 - Toll Free : 986 RESI-ENV Pager : 303-509-2098 INVOICE TO: (IF DIFFERENT)

Job # 2 3 > (22)

CONTACT INFORMATION:	Contact Closude Murray	Phone: 303, 480, 4101	Fax:	СеШрадег:	Final Data Deliverable Email Address: 1 K a N ( P. N + (G) ( M.CCOMSU) +QV+5, COM		
CONTACT I	Contact: Jasan Kahlart	Phone 303,980, 4101	Fax 303, 980, 4107	Cellipager: 303, 120 SOG, 3420 Cellipager:	Final Data Deliverable Email Address:		
INVOICE TO: (IF DIFFERENT)	Company:	Address:					
	ompany: RMC CONSULTANTS INC.	10101 101 HB + 41 1011 A	What Ridge CO 80033		roject Number and/or P.O. #: (512, 006, 015, 0001	roject DescriptionLocation: Rallins ulli た, Cの	

ASBESTOS LABORATORY HOURS Weekdays #7am =7pm   state   1 and	27,522 27,62 27,62 27,	6 (5 (1) 6 6 (1) 6 (1) 6 (1) 6 (1)	REQU	ESTE	REQUESTED ANALYSIS	YSIS	**************************************	6 \$16.5 22.5782 2.632.1 46.6851 52572 525272 41.6855	20 CM 20 CM	ALID	MATRI	VALID MATRIX CODES	500'A 50 600'A 50 500'A 50 50 50'A 50 50'A 50 50'A 50'A 50'A 50'A 50'A 50'A 50'A 50'A 50'A 50'A 50'A	LAB NOTES:	S
PLM / PCM / TEM RUSH (Same Day) PRIORITY (Next Day) STANDARD		_	_						4	Air = A		Bulk = B			
(Rush PCM = 2hr, TEM = 6hr.)			_						ฉั	Dust = D		Paint = P			
CHEMISTRY LABORATORY HOURS. Weekdays. dam - 5pm									Ñ	Soil = S		Wipe = W			
Metal(s) / Dust RUSH 24 hr. 3-5 Day	.tr								Swab =	NS = q		F = Food			
ţ			u			uoili		uc	Drinking Water = DW	Water		Waste Water = WW	ww		
Fume Scan / TCLP Con	) '-/		308			aoific					O = Other	J.			
24 hr 3 day 5 Day	+ '(		slate						**ASTM	E1792	approved	E1792 approved wipe media only**	ıly**		
JURS: We	g report, Po 7402, ISC SO-Indirect		Fume, Me			+/- or Qi tification uantificatio	uantification ntification	ation , Qua							
"	,li ləv		(s		-/+	neuD	D 10								
Trimaroush times establish a laboratory priority, subject to laboratogroblane and are not guaranteed. Auditorial fees	героп, А, Le <i>r</i>		nalyte(,			10 -,	-/+		əwn				1972 F 1649 F 1257 E	19624 19624	4,832.55 20,825 20,634 20,235 200.55 20,435
1. (株)	horts -	. 7400v stoT - Tota	יר <b>פ -</b> ∀	HICE -	StO iloo.	9 oidore + :iloo. emolilo	aurėus:	D S/EB/S Old: +/	ple Vol	x Code	Date				6
Client sample ID number 1 222 22 22 22 22 22 22 22 22 22 22 22	Mat		AT3M		Ε.	1 OBC	\ \ I		. 1		Collected	-			CONTRACTOR  CONTRA
Kwc - 0702 - 02	7									Ω	6/6/17	77 27	<u>ナ</u>	<b>5744</b>	2
	X	ingke (n. etc. gestaffe fre gestaffe (n. etc. gestaffe (n. etc. gestaffe (n. etc. gestaffe (n. etc.		Lipture de Caracterio Caracterio Caracterio Caracterio Caracterio	145 88 4 8 8 8 1 8 5 8 8 8 8 1 1 1	SAFEL FINE SAFEL ÉTIL SAFEL ÉTIL SAFEL SAFEL SAFEL SAFEL	MESSAGE SERVER	CONTRACTOR	managan man man managan man managan managan managan man man managan man man man man man man man man man m	8		001	0	TO THE SECOND SE	8
RWC- 0702- 04	~									B (		1158	90	(J	. <u>.</u>
The second secon	X	1 12 10 10 10 10 10 10 10 10 10 10 10 10 10	LEGAL COM- CENTRO COM- COM- CENTRO COM- CENTRO COM- CENTRO COM- COM- CENTRO COM- CENTRO COM- CENTRO COM- CENTRO COM- COM- CENTRO COM- COM- COM- COM- COM- COM- COM- COM-	CORP. TOR. - CORP. - CORP. TOR. - CORP. T	600 (000) 6-200 (000) 6-200 (000) 6-200 (000)					8 (	plak, satis	). S	က္ခ	COLUMN TO SECURE OF THE SECURE	
12mc-0702-06	×									<u>-</u>		12	1210		53
The state of the s	×				125 to 2020 125 to 2020 125 to 2020 125 to 2020 125 to 2020	entraletea serraletea etxicosco superales servanan			mentely a space a spac	BIL			9221		Ä
13wc-0702-08	<u>~</u>									1 8		+221	14		S
An experience of the control of the		en engel or englant open englant open		angeringsv retspering setspering setspering	est cabbolist estedente	STREETS OF		DISTRICTOR SECURITOR SECUR		3 1	eren eren Eren eren Eren eren er				8
	~									18		12	235		(C)
The second secon	diment diment	1235211 1235211 14352111 123521111 123521111	602.045.1 602.045.1 602.045.1 602.045.1	o calbando socialista	.52253570.7. 20125370.7. 27253727373 212537374	erelianes esperatores esperatores esperatores		FERRITARIA FRANCIS NA FRANCIS NA FRANCI	ertologo de Lasto espeta e Lasto espeta e Lasto espeta Lasto espeta Lasto espeta Lasto espeta Lasto espeta	1 9	•	A CHARLES	522		8
Number of samples received: (Additional samples shall be listed on a	on attached long form.	ng form	~												

NOTE: REI will analyze incoming samples based upon information received and will not be responsible for errors or omissions in calculations resulting from the inaccuracy of original data. By signing client/company representative agrees that submission of the following samples for requested

	- F - J - O	Harry Mar	4			Coto C	Sen 21.5.	Semela Condition.	90 60 80	September	Intact
Kellndul	Relinquished by:	- 2/10				Date: Hitte.	) )	Sample Condition		200	
Laborato	aboratory Use Only	7						Temp. (F°)	Yes/No	Yes/No Yes/No	Yes/No
Received By	3y:		Date/Time:	Time:		Ğ	Carrier.				
Results:	Contact	Phone Email Fax	Date	Time	Initials	Initials Contact	Phone Email Fax	Date	Time	Initials	S
	Contact	Phone Email Fax	Date	Time	Initials	Initials Contact	Phone Email Fax	Date	Time	Initials	2

Due Date:	Due Time:

# 5801 Logan St. Denver, CO 80216 • Ptr. 303 964-1986 • Fax 303-477-4275 • Toll Free :866 RESI-ENV Pager : 303-509-2098 INVOICE TO: (IF DIFFERENT)

Job # 2.33-(2.2.

CONTACT INFORMATION:

Company:	RMC (on 54) +00 +5 7 8C	1 2 1 2 5	Company	any:			Contact:	Contact: Jason	140 HOX			_	Clarate Mr	Mulhay	
	12,295 W HB	かけいつ 大子 かか	Address	:83:			Phone:	303.9	980,410			Phone: 303	5	017	
^	1	CO 800 23					:Xa	303,9	4 v 0 8	子0		Fax:			
	1000						Cell/pager:	303.	506.3	.3420		Cell/pager:			
Project Number	Project Number and/or P.O. #: 612,	612,006,013.0001					Final Dat	a Deliverable E	Final Data Deliverable Email Address:	Kalhert	@ T-X	CMC-C	CONSULTANTS	24+8, C	¥
Project Description/Location:		ROWINS UNITE, CO							!						
ASBEST	NS I ABORATORY	ASBESTOS / ABORATORY HOUBS: Weekdays 7am - 7pm	Section of the sectio	100 (100 (100 (100 (100 (100 (100 (100	10 PER 10	CONTROL OF THE PARTY OF T	EQUEST	REQUESTED ANALYSIS	YSIS	COSTRE CO	TWX	VALID MATRIX CODES	CODES	LABN	LAB NOTES:
Of M DOM ( TEM	(TEM RI	RISH (Same Day) PRIORITY (Next Day)	Oav	X STANDARD			_			_	Air = A	4	Bulk = B		
		(Rush PCM = 2hr TEM = 6hr.)	1								Dust = D	0	Paint = P		
CUERROL	VACTABODATODY	CHEMISTRY   A BORATORY HOLIRS Weekdays 8am - 50m	2007. 2007.	- 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1	# ## c \$1150 -1 #1 \$1151						= lioS	s=	Wipe = W		
Metal(s) / Dust	Just	RUSH 24 hr. 3-	8 8		יג'						Swab = SW	SW	F = Food		
RCRA 8 / R	RCRA 8 / Metals & Welding			**Prior notification is			ut				Drinking Wa	er = DW Wa	Drinking Water = DW Waste Water = WW	>	
Fume Scan / TCLP	1/TCLP		_10 day	required for KUSH turnarounds.**			30S		201111			O = Other			
Organics		24 hr 3 day 5 [	5 Day				etale		uo		**ASTM E1	'92 approved	**ASTM E1792 approved wipe media only**		
MICROBI	OLOGY LABORAT	MICROBIOLOGY LABORATORY HOURS: Weekdays: 9am - 6pm	am - 6pm	CETTER CONTROL		alire	M '€		noi iteati iteai	no '					
E.coli 015	E.coli O157:H7, Coliforms, S.aureus			3-5 Day		AH8	un <u>.</u>		ficat itasti antif						
Salmonell	Salmonella, Listeria, E.coli, APC, Y & M	48 Hr.	3-5 Day			SI '	j 6u		ianti Qu Qu	Boff					
Mold		RUSH	24 Hr 48 Hr	r 3 Day 5 Da	) 'I	NSC.	ible/	/+ :	Qu ot ot	itnət			-		
Turnarour	dames establish a labor	atory priority, subject to happratory vol	lume and are not	granated Additional	pod	-010 740	Μ, 1	ZH:	-/+ -/+	PI	อน			40 41 42 43 44 44 44 44 44 44 44 44 44 44 44 44	83 83 83 84 85 85 85 85 85 85 85 85 85 85 85 85 85
	ACCORDING TO COMPANY T		idays 🕯		ورو الر 10	iM , ,A0i	СГБ	/+ : /91:1	:su :su -/+	· -/+		:G12			2
Special Instructions	structions:				ods -	insup - 740 oT - 1	- 8, Т 48, Т АЦС	nomla O iloo. shətsi	oidone .iloo. niolilo: uenue.		V əlq sənA oO xi	nietno Oate		Ž.	Number (taboratory
	80% S2828 S8 159 159 2		ASSESSED AND ASSESSED	2015 1254 1564 1564 1565 1565 1565 1565 1565 15		CW ewi	ADS	] -	NEIOI OGY	MAR	/ (¬)	Collected	ted Collected	150 (250) 23 (25) 23 (25) 4 (3) (25)	Franklike Franklike Franklike Franklike Franklike Franklike Franklike Franklike Franklike Franklike Franklike Franklike
ien s	וע		** :::1		4	3	4			  -		┡	Ľ	101	NO W
<u>-</u>	RWC-0702-				×					2 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	10 12 12 13 13 13 14 15 15 15 15 15 15 15 15 15 15 15 15 15	ا ر دا د	ra	7	-
u Ž	OLONG											PROPERTY OF THE PROPERTY OF TH		minimum central centra	ာ ၅
Š	・このナシャンさ				メ						<u> </u>		CK21		9
-	288	100 mm m	100 C	TO THE PART OF THE	100 20 100 20 20 20 20 20 20 20 20 20 20 20 20 20 2	\$2.33 \$2.53	1791319 1791319 1791319 1791319 1791319 1791319 1791319	\$241.6 151.5	\$20,000 1979-0-0 1979-0-0 1979-0-0 1979-0-0 1979-0-0	110 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	8	\$10.5 (5.0) \$10.5	N. S. J.	CONTROL OF CONTROL OF CONTROL OF CONTROL CONTR	<b>(</b> )
4 ک	9 2 6 0 1 3		1000 1000 1000 1000 1000 1000 1000 100		ر د ا	12:1 17:1 17:1 17:1 17:1 17:1	erie Res Res Res Res	18.1 19.1 19.5 19.5 19.5 19.5 19.5 19.5 19	20 20 20 20 20 20 20 20 20 20 20 20 20 2	150 201 201 201 201 201 201 201 201 201 20	79- 235 232 61- 239- 45- 45- 200-				707
2	ローエレーンろど				۷		1	22.0	× 90 × 91	6 x 5 x 5 x 5 x 5 x 5 x 5 x 5 x 5 x 5 x	0 x 0 m 2 m 2 m 2 m 2 m 2 m 2 m 2 m 2 m 2 m	% 33 33 34 34	2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1	200 101 200 200 200 200 200 200 200 200	58.5
ර <u>ු</u> ඉ	RNC-184-02	The second secon			X.			SCHELLY SAFETO S	en eden en eden en en en en en en en en en			2000	A PROPERTY OF THE PROPERTY OF	11-14-15 11-	50
7					-										0.00
	partition of the partit	The state of the s			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	20 20 20 20 20 20 20 20 20 20 20 20 20 2								ACCEPTANT OF THE PROPERTY OF T	SOUTHERN STORES
σ									-						į,
	は、	852521E7 856196C	2012/2012 2012/2		200 (200 ) 200 (200 )	15 15 12 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	A CERT OF	1971 (1984) 1971 (1984) 1971 (1984) 1971 (1984) 1984 (1984)	STATE OF THE STATE	60 mm bad 5 mm	SALES AND	FTTTT STYLE  FTTT	CONTROL OF THE CONTRO	STATES OF THE ST	
Nimberof	Number of samples received:	8	(Additional s	amples shall be list	ed on attache	ed long form.)									
NOTE:	REI will analyze incoming sa	NOTE: REL will analyze incoming samples based upon information received and will not be responsible for errors or omissis	d will not be respondices agreement wi	sible for errors or omissions the payment terms of NET.	ns in calculation 30 days, failure	nns in calculations resulting from the inaccuracy of original data. By signing dient/company repr 30 days, failure to comply with payment terms may result in a 1,5% monthly interest surchange	ne inaccuracy	of original da may result in a	a. By signing cli	ent/company naterest surchai	presentative ag ge.	ees that submis	sion of the following	ons in calculations resulting from the inaccuracy of original data. By signing client/company representative agrees that submission of the following samples for requested 30 days, failure to comply with payment terms may result in a 1.5% monthly interest surchange.	sted
20,000		MINING TO STATE OF THE PARTY OF	100					7	7, 1	(35	$\overline{}$	- Conditions	5	poledo	Infact
Relindu	Relinquished By:	7728	)    			Date/Ime:	بل اق	ا د		- 1	Ţ		S 10 X		Yes / No
Laborator Received By	Laboratory Use Only/ Received Bv:		Date/Time	ne:			Carrier:				d lear			1	
Results:	Contact	Phone Email Fax	Date	Time	Initials	Contact		Phone E	Email Fax		Date		Time	Initials	
	Contact	Phone Email Fax	Date	Time	Initials	Contact		Phone E	Email Fax		Date		Time	Initials	